

# NSP 120 CASE HISTORY

MULTI-VENDOR EPOXY SOLUTIONS

## Project Information

Johnston County Water Treatment Authority

Lift Station Wet Well - Chemical Protection (Wastewater)

## Product Information

Primer: Concrete sealer @ 200 sq./ft./gal.

Intermediate: Epoxy filler.

Finish: NSP 120 coating sprayed @ 20-25 mils.

## Surface Preparation

Concrete - hydroblasted (3,500 psi) and decontaminated with bleach.

## Follow Up Inspection or Update

Date Applied - August 2002.

Result - invited to bid on three more lift stations.

Read the Material Safety Data Sheet before using

c14lift.pm6