

NSP 120 CASE HISTORY

MULTI-VENDOR EPOXY SOLUTIONS

Project Information

City of Firth - Firth, ID

40,000 gallon capacity elevated water tank (potable water)

Product Information

Primer: None used

Intermediate:

Finish: One coat of NSP 120 epoxy coating applied at a minimum 8 mils dry film thickness

Surface Preparation

Steel substrate sandblasted to SSPC-SP10 Near White Metal

Follow Up Inspection or Update

No inspection, but no problems have been reported.

Overall Condition of Completed Project and/or Follow Up

Read the Material Safety Data Sheet before using

c3pm6