

# NSP 120 CASE HISTORY

MULTI-VENDOR EPOXY SOLUTIONS

## Project Information

Hyprescon, Inc. in Canada

Concrete Pipe Lining for Municipal Sewage Main.

## Product Information

Primer: NSP 120 Coating @ 300 sq./ft./gal - minimum 6 hour cure time before intermediate coat application.

Intermediate: NSP 120 Coating @ 10 mils, tile red.

Finish: NSP 120 Coating @ 10 mils, black

## Surface Preparation

Precast Concrete Pipe (54" diameter) was blasted to SSPC-SP 7 Brush Off Blast Cleaning.

## Follow Up Inspection or Update

Date Applied - January 2000, March 2000 and August 2000.

Overall condition - Coating system is performing as expected in good condition. Hyprescon has specified the same system in other applications. Ease of application, chemical resistance and cure time were a plus for this type of project.

Read the Material Safety Data Sheet before using

c11Sewer.pm6